



**MGM INSTITUTE OF HEALTH SCIENCES
CENTRAL PURCHASE DEPARTMENT (CPD)**

Plot 1 & 2, Sector -1 Kamothe, Navi Mumbai 410209

eTender of Excavation Work

Tenders invited from reputed Contractor of Excavation Work at MGM Hospital, Kalamboli in the format given below:

Name & Address of Vendor: _____

Sr. No.	Name of Item with Specifications	Unit	Rate per Unit (Excluding. GST)	GST %
A	Excavation Work			
1	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material upto a distance of 50 meters. Beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary backfilling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m) By Mechanical Means.	M3		
2	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material upto a distance of 50 meters. Beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary backfilling, ramming, watering including shoring and strutting etc. complete. (Lift from 1.5 m to 3.0m) By Mechanical Means.	M3		
3	Excavation for foundation in hard murum including removing the excavated material upto a distance of 50 meters. Beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary backfilling, ramming, watering including shoring and strutting etc. complete. (Lift from 3 m to 4.5m) By Mechanical Means.	M3		

Sr. No.	Name of Item with Specifications	Unit	Rate per Unit (Excluding. GST)	GST %
4	Excavation for foundation in soft rock and old cement or lime masonry foundations including removing the excavated material upto a distance of 50 meters. Beyond the building area and stacking and spreading as directed, including dewatering, preparing the bed for the foundation and necessary backfilling with available earth/murum, ramming, watering including shoring and strutting etc. complete. (Lift from 4.5 m to 6m) By Mechanical Means.	M3		
5	Shifting of Excavated material from MGM Hospital Kalamboli to MGM Campus Kamothe, near about distance 2.5Kms. Away from construction site.	1 M3		
Total Appx. Qty: 1875 Sq.m x 6 meter depth =11,166 m3				
B	Excavated Material Shifting	8374 M ³		
Terms and Conditions:				
work completion period:				
Payment Terms:				
Kindly email your lowest quotations for above items with your terms and conditions as well as applicable Brochure / Catlog, Client list with installation Year and their Contact numbers to etenders@mgsuhs.com only.				
Date:		Signature of Tenderer:		
Seal		Name:		
		Designation:		
		Email ID:		
		Mobile No.:		
		Full Address:		