



MAHATMA GANDHI MISSION TRUST
MGM INSTITUTE OF HEALTH SCIENCES, CENTRAL PURCHASE DEPARTMENT (CPD)
Plot 1 & 2, Sector -1 Kamothe, Navi Mumbai 410209
eTender of Civil Maintenance Work

eTenders invited from Contractors with registered Licence and experience of Civil maintenance Labour Work for Rate Contact of new work and maintenance work to be carried out in the MGM Campus, Navi Mumbai in the format given below:

Name & Address of Vendor: _____

Tender form For Civil Maintenance work

Sr. No.	Nature of work	Unit	Rate
1	Excavation (Manual) in soil, Soft Murum.removing excavated material shifting stacking & leveling within 50mtrs from building	C.ft	
2	Excavation (Manual) Soft Rock.	C.ft	
3	Excavation in Hard Rock using Compresor	C.ft	
4	Back Filling of excavated material manually	C.ft	
5	Excavation using JCB from upto 3mtrs depth & again back filling	C.ft	
6	Excavation Using Hyadraulic Excavator upto 4mtrs depth & again back filling	C.ft	
7	Debries of Construction shifting within 500mtrs. In MGM Campus area	C.ft	
8	P.C.C work preparing level surface in level with compaction & concrete PCC curing complete	Sq.ft	
9	Soling 230mm size duber & gap filling on metal greet powder watering & compaction complete	Sq.ft	
10	Concreting for road making for pavement with expansion joint every 6 mtrs to stop crack development & curing complete.	Sq.ft	
11	100 mm Brick Work up to 3.6mtrs height with mix mortar in preparation of 1:6 & curing complete with concrete band include scaffolding	Sq.ft	
12	150 mm Brick Work - same as above	Sq.ft	
13	230 mm Brick Work - same as above	Sq.ft	
14	100 mm Block Work up to 3.6mtrs height with mix mortar in preparation of 1:6 & curing complete with every 1 meter height provide concrete band with reinforcement	Sq.ft	
15	150 mm Block Work same as above with every 1.5 meter height provide concrete band with reinforcement	Sq.ft	
16	230 mm Block Work - same as above with half of the height provide one concrete band with reinforcement	Sq.ft	
17	100mm Coping of concrete 1:2:4 with steel bar every 1.5mtrs height	R.ft	
18	Brick pillar masonry work in cement mortar curing & complete 15" x 15" & 18" x 18"	C.ft	
19	Plaster work internal up to 4 mtrs height with scaffolding in mortar 1:4 for internal wall Plaster & curing complete	Sq.ft	
20	Plaster work External Wall in Two Coats with curing complete	Sq.ft	
21	RCC Lintel size 300 x 230 or 350 x 230mm concreting with centering, fitter work, scaffolding & curing complete	R.ft	
22	RCC Footing work with concreting, centering, fitter work, scaffolding & curing complete	C.ft	
23	RCC Pardi work with concreting, centering, fitter work, scaffolding & curing complete	C.ft	
24	RCC Beam work with concreting, centering, fitter work, scaffolding & curing complete	C.ft	
25	RCC Slab (100 to 125mm) work with concreting, centering, fitter work, scaffolding & curing complete	Sq.ft	

Sr. No.	Nature of work	Unit	Rate
26	RCC Chajja 0.75 mtrs outer with concreting, centering, fitter work, scaffolding & curing complete	R.ft	
27	R.C.C Foundation with concreting, centering, fitter work, scaffolding & curing complete	C.ft	
28	IPS work in mix mortar & in with level curing complete.	Sq.ft	
	Repair Maintenance work		
29	Old Wall Dismantling & Rabbit Material Shifting to Ground level	Sq.ft	
30	Old RCC work (Columns, Lintel, Slab, Beam, Pardi) Dismantling, Steel Remove & Rabbit Material Shifting to Ground level	C.ft	
31	Big Chamber (3'x1'x6'deep) (Brick work + Plaster Finishing)	Nos	
32	Small Chamber(1'X1'X6'deep) (Brick work + Plaster Finishing)	Nos	
33	Old Brick bat Coba Breaking & Material Shifting	Sq.ft	
34	W/P Base Coat For WC and Bath	Sq.ft	
35	Parking -Soiling & Material, Compaction and Leveling	Sq.ft	
36	Core Cutting 2", 3" & 4" Per Inch	Per Inch	
37	Murum Cutting & Leveling	C.ft	
38	Soiling Metal No-1 & Spreading Stone Dust Leveling, Curing and Rolling	Sq.ft	
39	Duct R.C.C Jali Fitting	Sq.ft	
40	Brick Bat Coba & Water Proofing	Sq.ft	
41	Exhaust Hole Cutting and Finishing	Nos	
42	Drainage Pipe Line Fitting Long Way Hume core Pipe 6"	R.ft	
43	Drainage Pipe Line Fitting Long Way Hume core Pipe 9"	R.ft	
44	Drainage Pipe Line Fitting Long Way Hume core Pipe 12"	R.ft	
45	Drainage Pipe Line Fitting Long Way Hume core Pipe 24"	R.ft	
46	M.S railing Remove	Sq.ft	
47	Concrete Cutting	Sq.ft	
48	China Chips Fitting	Sq.ft	
49	Base Coat Work	Sq.ft	
50	Scaffolding (Bamboo) Work	Sq.ft	
51	Scaffolding ('H' Frame) Work	Sq.ft	
52	Toilet / Bath Water Proofing with Brick Bat Coba	Sq.ft	
53	Steel Cutting Fitter Charges-Per Day	Per Day	
54	Breaker Machine Charges - Per Day	Per Day	
55	Old Plaster Remove and Material Shifting	Sq.ft	
56	Door Frame Remove & Wall Dismantling and Material Shifting	Sq.ft	
57	Rain Water Long Pipe Fitting-4"	R.ft	
58	Rain Water Small Exit Pipe	Nos	

Sr. No.	Nature of work	Unit	Rate
59	Double Grove Work	R.ft	
60	M.S Square Pipe (150x150) fitting	Nos	
61	R.C.C Pole Casting	Nos	
62	Chain Link Jali Fitting with Cement Nails,Welding and Drilling Work	Sq.ft	
63	UCR Masonry Work	C.ft	
64	Pointing Work	Sq.ft	
65	Wall Grove Cutting Work	R.ft	
66	Chamber Dismantling Work	Sq.ft	
67	JCB Work	Hrs	
68	Dumper work	Hrs	
69	Earthing Chamber (2'x2'x1') (Brick work + Plaster)	Nos	
70	R.C.C Cover Fitting Work	Sq.ft	
71	POP Partition Remove and Shifting Work	Sq.ft	
72	Door Frame Fitting Work	Nos	
73	Rain Water Exit Cement Pipe Fitting	R.ft	
74	Repairing work labour supply		
	Meson	Per Day	
	Helper	Per Day	

Maintenance of civil work rates should be given considering following conditions

- 1) work quantity may be minor patchup 1/4 brass & 1/2 brass or 1 brass. Whatever may be quantity rate will be same.
- 2) Work include lead of material may be maximum 250 meter & rise from ground to 8th floor. Rate of work will be same.
- 3) If work may be of height above 12 feet same rate will be consider include scaffoldingcost which consider in quoted rates.
- 4) After completion of all civil work curing work has to carried by contractor 7 to 8 days.
- 5) Safety of labour should be maintained by contractor
- 6) In Concreting & RCC work the formwork & Scaffolding should be of contractor. Only water & electricity provided by MGM.

Terms and Conditions:

GST %

Payment Terms

Kindly email your lowest quotation as above to only etenders@mgsuhs.com along with your terms & conditions, client list, Work done experience with Work Orders, etc.

Date:	Signature of Tenderer:
Seal:	Name:
	Designation:
	Email ID:
	Mobile No:
	Full Address: