## MGM MEDICAL COLLEGE G + 3 & G + 4 FLOORS, ELEVATOR

Α	MGM Medical College Building, Plot No. 1 & 2, Sector-1, Kamothe, Navi Mumbai - 410 209.		
1	Number of Lifts/Elevators Required	01 Nos.	02 Nos.
2	Number of Persons	15 Persons	15 Persons
3	Lift Shaft Size	2.30 M x 2.35 M	2.30 M x 2.35 M
4	Building floors	G + 3 Floors	G + 4 Floors
5	Doors Opening	4 Openings	5 Openings
6	Floors Heights		
6.1	Ground floor	12'. 7"	12'. 7"
6.2	1st floor	14'. 7"	14'. 7"
6.3	2nd floor	14'. 11"	14'. 11"
6.4	3rd floor	14'. 11"	14'. 11"
6.5	4th floor	N.A.	12'. 2"
7	Machine room	Available	Not Available

Site Engineer MGM Kamothe, Navi Mumbai.

## MGM SCHOOL NERUL, G + 4 FLOORS ELEVATORS

А	MGM Nerul School Building, Plot No. 14, Sector-8, Nerul, Navi Mumbai. 400706.		
1	Number of Lifts/Elevators Required	2	
2	Number of Persons	15	
3	Lift Shaft Size	1.75 x 1.65 mtrs.	
4	Building floors	Ground + 4 floors.	
5	Doors Opening	Ground & 1st floor Staircase side (Front Side) & 2nd to 4th floor Passage side (Back Side)	
6	Floors Heights in mtrs.		
6.1	Ground floor	3.950	
6.2	1st floor	3.600	
6.3	2nd to 4th floor	4.200	
7	Machine room	Available	

Site Engineer MGM Kamothe, Navi Mumbai.

## ${\bf MGM's\ STUDENT\ HOSTEL\ BLDG.\ KHARGHAR,\ G+4\ FLOOR\ ELEVATORS.}$

А	MGM Proposed Student Hostel Building, Plot No. 72F, Sector-11, Revenue Village, Kharghar, Navi Mumbai, Tal. Panvel, Dist. Raigad.		
1	Number of Lifts / Elevators Required	1	1
2	Number of Persons	15	10
3	Lift Shaft Size	1750 x 2750mm	1700 x 1650mm
4	Building floors	Ground + 4 Floors	
5	Floors Heights in mtrs.		
5.1	Ground & 2nd to 4th floor	3150	
5.2	1st floor	3600	
5	Machine room	Available	

Site Engineer MGM Kanothe, Navi Mumbai.

## MGM DENTAL COLLEGE EXTN. BLDG., G + 7 FLOOR ELEVATOR

А	MGM Dental College Extension Building,Plot No. 1&2, Sector-1, Kamothe, Kalamboli Highway, Tal. Panvel, Dist. Raigad. 410 209.		
1	Number of Lifts/Elevators Required	1	
2	Number of Persons	15	
3	Lift Shaft Size	2.10 x 2.10 mtrs.	
4	Building floors	Ground + 7 floors.	
5	Floors Heights in mtrs.		
5.1	Ground floor	3.600	
5.2	1st, 2nd, 4th, 5th & 6th floor	3.800	
5.3	3rd floor	4.350	
5.4	7th floor	3.750	
6	Machine room	Available	

Site Engineer MGM Kamothe, Navi Mumbai