



MAHATMA GANDHI MISSION TRUST
MGM INSTITUTE OF HEALTH SCIENCES, CENTRAL PURCHASE DEPARTMENT (CPD)

e-Tender for Providing and Fixing Hospital Furnitures

Tenders invited from reputed Manufactures or their authorised distributors / dealers of Providing and Fixing Hospital Furnitures at MGM Hospital, Sanpada, Navi Mumbai, in the format given below:

Name & Address of Vendor: _____

BILL OF QUANTITIES FOR INTERIOR WORKS OF PROPOSED MGM HOSPITAL & RESEARCH CENTER GROUND FLOOR - NAVI MUMBAI

1 DOORS WINDOWS & ALLIED WORKS

NOTES :

The rates quoted by the Contractor for items under this head shall be inclusive of the following:

- 1) All labour, materials, equipments, etc. for carrying out the work as directed at all heights and levels.
- 2) Wood preservative treatment to rough frame work in partitions and to embedded part of wood work in masonry/concrete.
- 3) Providing, fixing frames and shutter with hold fasts and fixtures.
- 4) 3 coats of ready mixed enamel painting of approved colour including appropriate primer of approved make.
- 5) Rebates, joints, chamfers, mouldings, grooves, beads, laps, rounded angles, notches, and providing nails, screws, pins, etc.
- 6) Shutters of doors, windows and fan lights shall be measured net in a closed position covering rebates of the frame.
- 7) M.S. hollow frames shall be filled with mortar of masonry while doing masonry work. No extra shall be paid.
- 8) Windows shall be fabricated as per actual opening sizes available at site and as directed.
- 9) All screws for Aluminium works will be Chromium plated steel screws or Aluminium screws as directed.
- 10) All Aluminium sections shall have protective covering until completion of other civil works, duly cleaned before handing over. Aluminium
- 11) All glazing shall be fixed after completing of other works in surrounding area to avoid damage.
- 12) For door frames wider than 150 mm, the frame will be in 2 pieces as per detailed drawings and both frames will have independent hold

Sr. No.	Particular	Qty	Unit	Rate (Supply)	Total (Supply)	Rate (Labour)	Total (Labour)	Total Supply + Labour
1	DOORS WINDOWS & ALLIED WORKS							
1.1	Providing and fixing Door Frame in position to line and level in Malaysian/Ghana Teak wood frame out of specified sections finished size 135mm x 65mm as per drawing details including cutting rebate, finished in 3 coats of natural polish matt finish(TUFFWOOD OR EQUIVALANT) matching the shutter laminate finish of approved colour & shade as per Architects instructions.	140.00	Rmt		-			
1.2	Providing and fixing 19 mm thick QUARTZ STONE of approved quality and shade in door frames in 2 pieces to form rebate for toilets in CM including half rounding edges, edge polishing etc. all complete. Total Stone width for the 2 pieces up to 200 mm wide suitable for 150 mm thick block masonry with plaster or tile dado.							
	DOOR FRAME - to toilet	63.00	Rmt		-			
1.3	Providing and fixing solid core flush doors made of 38mm thk marine ply finished flush Doors to be finished in 1mm thk approved laminate on both the sides as per design and detail . The door to be fitted on 4 Nos. 4" long SS Hinges (with SS pin) of approved make and completed with Brushed 300mm SS handles of approved make as per the approval of the architect. Cost to be inclusive of all necessary hardware like locks, tower bolts, door stoppers, PVC bushes etc. of approved make and as specified in the drawing. All exposed edges to be finished with Malaysian/Ghana Teak wood beading as per details provided, to be finished with 3 coats of sprayed polish. Door frames, concealed closers ,floor spring to be paid separately under relevant items. (All doors)	66.00	Sqm		-			
1.3.a	Same as above item no:7.3 but for sliding Door	9.00	Sqm		-			
1.3.b	Extra for providing and fixing 2mm thk lead lining to exposed wooden surface of door shutters including providing 6 mm thick marine ply and 1 mm thick laminate as directed, including all necessary glue, screws etc all complete.	20.00	Sqm		-			
	Approved Make for Door Hardware: Dorma, Hafele, Geze, Assa Ablloy Approved Make for Metal Fire Door: Shakti Hormann, GWS, JSW, Signum, Tata Pravesh Approved Make for Wooden Fire Door: Promat, Kenwood, Tuffwood / V-Cam Approved Makes for Laminte: Merinolam, Greenply, Greenpanel, Royal Touch, Formica. Approved Makes for Flush door: Greenply, Anchor, Century Approved Makes Glass : Saint Gobain, AIS Glass, Modi Float							

Sr. No.	Particular	Qty	Unit	Rate (Supply)	Total (Supply)	Rate (Labour)	Total (Labour)	Total Supply + Labour
1.4	Providing and fixing wooden fire rated door frames as per BS: 476 part 22, IS:3614 Part II as per the prototype certified by CBRI Roorkee or equivalent lab, frame to be made out of fire rated wood as approved of section 120mm x 70mm for fire resistant doors of 120 minutes fire rating, with heat activated intumescent fire seal strips of size 02 nos. x 10 x 4mm (for smoke sealing) provided in grooves on all three sides of the frame with one coat of approved brand of fire retardant primer including two coats of fire retardant paint FRS 881 un thinned on cleared hard wood surface of door frames (@3.5 sq.m. per litre per coat) including preparation of base surface as per recommendations of manufacturer to make the surface fire retardant, including fixing the frame with 8 nos. 100mm long, 10mm dia metal dash fasteners complete as per directions of the Engineer in charge	25.00	Rmt					
1.5	Supply & fixing of fully insulated wooden fire door of approved make of 120min. fire rating, of minimum 50mm thickness, comprising of 75mm x 44mm hardwood internal timber frame work, with infill insulation of 20mm thick of 96 kg/m ³ , wool insulation, coated with intumescent coating on both sides for insulation. The coated insulation shall be sandwiched between min 12mm thick Non Combustible (Calcium Silicate) Boards on both sides (edge to edge on internal Hardwood frame) and clad with 3mm thick Commercial ply & 1mm thick Laminate (approved shade and colour) on both sides, with 50mm x 14mm exposed teak wood lipping all round the shutter. The shutter shall be fitted with fire & smoke intumescent seal of size 20 x 4mm on all the three sides except bottom. The pasting of the ply / laminate should be done using automatic machine and should be free from any nails or perforations	17.00	Sqm					
	The board shall be Resistant to vermin, mould growth, minor impact, abrasion and short term water attack and shall be Off -white in colour with a smooth surface suitable to receive most forms of decoration having following technical characters i.e.; The Construction design similar to NWD12050 and similar to the design tested as per BS 476 part 22 and IS 3614 Part II, at CBRI, Roorkee or equivalent lab. The shutter can be provided with appropriate openings for view panel glass, if required.							
1.6	Extra over for providing C shaped Matt finish SS 304 grade channel 40 x 25 mm edging to door shutter including necessary adhesives/screws etc all complete.	50.00	Rmt		-			
1.7	Extra for providing of vision panel of size 200 x 800 mm with 6 mm thk plain float glass and polished beading patti.	22.00	Nos		-			
1.8	Extra for providing and fixing Concealed door closers of approved make and model.	12.00	Nos		-			
1.9	Extra for providing and fixing PVC louvered ventilator to toilet door shutter as per detailed drawing.O/A size of ventilator--400mm X 150mm.	12.00	Nos.		-			

Sr. No.	Particular	Qty	Unit	Rate (Supply)	Total (Supply)	Rate (Labour)	Total (Labour)	Total Supply + Labour
1.10	Providing and fixing SS 304 grade kick plate and Middle Plate 200 mm high on one side or both side as directed including counter sunk screws, buffing etc. complete. Actual plate size used shall be measured and paid for.	26.00	Sqm		-			
1.11	Providing and fixing approved make UPVC section / track framed Window/Ventilators Partially fixed at and Partially openable using friction stay hinges, DGU glazing using 24 mm thick , hermetically dual sealed, double insulated glass panels comprising of 6 mm thick reflective (Grey / Bronze /Blue /Green) and toughened glass on the outside and 6 mm thick clear toughened float glass on the inside, with 12 mm air gap, complete, with butyl primary sealant and silicone secondary sealant, EPDM gaskets. flashing to ensure resistance to water penetration and air permeability, complete.							
1.11.a	O/A size :600mm X900 mm W1 (1 fixed Panel)	2.00	SQM					
1.11.b	O/A size :-1800mm X 1500 mm W2(2 Sliding Panels)	17.00	SQM		-			
1.11.c	O/A size :-2400mm X 1500 mm W3 (3 Sliding Panels)	62.00	SQM		-			
1.12	Providing and fixing fixed glazing using 10mm thick clear toughened glass and 12mm thk Quartz stone jamb all around , as per design ,etc complete.	10.00	Sqm		-			
					-			
2.00	PARTITION & PANELLING WORK.							
2.1	Providing and fixing 100mm thick bed head wall panelling in 12 mm thk ply panelling / Boxing of AL. box section 50x35 mm fixed over finished wall surface to hide over MGPS service line to BED Head panel assembly as per drawing details, finished in 1 mm thick laminate of approved shade. Including SS strips 10 m mx 3 mm thick, necessary hardware, glue etc all complete.(Location :- Patient Beds)	50.00	Sqm					
2.2	Providing & fixing in position Aluminium Composite Paneling (ACP) with framing of aluminium tube sections of min 1.5"x1" and 20 gauge at a spacing of 2' center to center both ways. ACP to be of bright silver shade in 2' width panels or distributed equally. ACP sheets to be fixed to the frame 3 M make adhesive along with mirror screws . Joints to be finished with silicon based sealant. ACP sheets to be min. 3mm thick with aluminium foil thickness to be min. 0.25 mm on both sides. Item includes providing additional sections to fix indoor AC units which will be installed at the higher position	32.00	Sqm					

Sr. No.	Particular	Qty	Unit	Rate (Supply)	Total (Supply)	Rate (Labour)	Total (Labour)	Total Supply + Labour
2.3	Providing and constructing Work table of size/module as per detailed drawing with 30mm thk table top 600mm[w] x 750 mm [ht] and front panel, sides, etc in 19mm thk commercial ply and finished in 1mm thick laminate on top and underside in 0.8mm thick. Edges to be in T.W beading polish.Supports, to be in ply boxing and finished in approved laminate.1 Nos. of pedestal 400mm wide for work table consisting of 2 drawers of 100mm ht balance openable shutter and skirting 100 mm ht finished in approved laminate as per detail drgs,all external surface finished in approved 1mm thk laminate and inside in 0.8mm thk white laminate. Cost to including handles,locks,hinges,telescopic channels, buffer with leveler, wire manager, etc complete.							
2.3.a	Linear Workstation [L]X600mm[W]x750mm[H]	15.00	RMT					
2.4	Providing and constructing Nurse Station / Resistration table of size as per Dwg. Working Table top in 19mm commercial ply and First Tier top and 2nd tier Work top finished in 6mm thk approved shade Solid Mineral Surface (Dupont) and including edges, 100 mm high skirting in 6mm thk Solid mineral surface material and all other surfaces in 1mm th laminate, Counter top as per Dwg in "L" shape with rounded edge. The rate to include three nos of pedestal units of size 400 x 600 x 750mm with 3 drawers and finished in approved laminate 1 mm thick for external surfaces and 0.8 mm thick laminate for internal surfaces. Rate also to include Pigeon hole type storage in 19mm marine ply of 300mm high at table top area. Cost also to include handles, telescopic channels, Buffer with leveler, 35 mm dia., wire manager etc. NURSE STATION.							
2.4.a	NURSE STATION (L MM) X 600MM WIDE x 750mm [H]	13.00	RMT					
2.5	Providing and fixing storage unit in 19mm marine ply for shutters, verticals and shelves, backing in 12 mm ply, all external surfaces finish in 1mm laminate , insides in 0.8 mm thick plain white laminate, cost to include for all hardware, lipping patti, handles, hinges, locks, etc.100 mm Skirting in ply with approved laminate to be provided at bottom. Area in elevation to be measured for payment (commercial Ply)							
2.5.a	400mm-600mm deep Full Ht Storage	14.00	Sqm					

Sr. No.	Particular	Qty	Unit	Rate (Supply)	Total (Supply)	Rate (Labour)	Total (Labour)	Total Supply + Labour
2.6	Providing and fixing in position Over Head storage 400mm deep ,750mm ht made out of 19 mm thk 6mm thk frosted glass shutter with matt finish aluminum profile handle at the bottom as per detailed drawing. The unit shall comprise of Shelves inside and recessed pelmet for light to be provided at bottom towards wall. All external finishes finished in 1mm thk laminate, insides in 0.8 mm thick plain white laminate, cost to include for all hardware, lipping patti, handles, hinges, locks, magnets etc complete.	3.00	Sqm					
2.7	Providing and fixing in position Soft board paneling on wall between desk / workstation top and overhead storages. Nominal framing of hard wood to be fixed on wall and 6 mm thk ply to be boarded on framing. 12 mm thk Soft Board to be boarded on ply finished with approved Fabric. 150mm high ply band finished in approved shade of 1mm thk laminate to be provided at bottom as per detailed drawing.	10.00	Sqm					
3.00	LOOSE FURNITURE							
3.1	Supplying and placing in position upholstered single seater sofa as per approval from client.	55.00	Nos					
3.2	Supplying and placing in position upholstered Triple seater sofa as per approval from client.	2.00	RMT					
3.3	Supplying and placing - Medium back chair with synchronized tilting mechanism with multiple locking systems, gas lift for height adjustment and nylon base with castor. Colour as approved from client.	20.00	Nos					
3.4	Supplying and placing corner table 450mm x 450mm as per approval from client.	10.00	Nos		-			
3.5	Supplying and placing center table 600mm x 600mm as per approval from client.	1.00	Nos		-			
3.6	Supplying and placing center table 1200mm x 750mm as per approval from client.	2.00	Nos		-			
3.7	Providing and fixing readymade Lockers in 3 door model made from CRCA sheets, with anti rust treatment and Powder coated in approved shade, Concealed flush type handle with inbuilt locking facility and provision for indexing and numbering of approved make.	2.00	Nos.		-			

Sr. No.	Particular	Qty	Unit	Rate (Supply)	Total (Supply)	Rate (Labour)	Total (Labour)	Total Supply + Labour
BILL OF QUANTITIES FOR INTERNAL FLOOR WORKS FOR MAHATMA GANDHI MEMORIAL HOSPITAL, SANPADA 3rd and 4th FLOOR WORKS								
1.1	Providing & making,supplying COUNTERS 600 mm deep with 12 mm thk SOLID MINERAL SURFACE top and storage below with verticals, sides, shelves and drawer units in 19mm thk commercial ISI Marked ply finished with approved 1 mm thk laminate on outside and 0.8mm white laminte on inside.Cost to include for solid mineral surface top and edges and and openable shutter with adjustable shelves as per drawing details all hardware, lipping patti, handles, hinges, locks, approved adhesive for fixing, etc. Refer dwgs for details. Area in elevation to be measured and paid for .(Hardware Make Hettich, Magnum or equivalent) (Mode of Measurement elevation area)	16	Sqm		-			
1.20	Providing & making,supplying COUNTERS 600 mm deep, Top and Edges finished in 12mm thk Solid Mineral Surface (Dupont / Aspiron) and laminate finished storage below with verticals, sides, shelves and drawer units in 19 mm thk commercial ISI Marked ply finished with approved 1 mm thk laminate on outside and 0.8 mm white laminte on inside. Cost to include for 12 mm thk corian (Dupont) top and 50mm high fascia patti, provision for fixing sink (SS sink not included in rate) and openable shutter with adjustable shelves as per drawing details all hardware, lipping patti, handles, hinges, locks, approved adhesive for Corian fixing, etc. Refer dwgs for details. Area in elevation to be measured and paid for. (Hardware Make Hettich, Magnum or equivalent). (Mode of Measurement elevation area)	17	Sqm		-			
TOTAL OF SECTION - FLOORING AND ALLIED WORKS					-			

Sr. No.	Particular	Qty	Unit	Rate (Supply)	Total (Supply)	Rate (Labour)	Total (Labour)	Total Supply + Labour
2.00	DOORS & WINDOW AND ALLIED WORKS							
	NOTES :							
	The rates quoted by the Contractor for items under this head shall be inclusive of the following:				-			
i	All labour, materials, equipments, etc. for carrying out the work as directed at all heights and levels.							
ii	Wood preservative treatment to rough frame work in partitions and to embedded part of wood work in masonry/concrete.							
iii	Providing, fixing frames and shutter with hold fasts and fixtures.							
iv	3 coats of ready mixed enamel painting of approved colour including appropriate primer of approved make.							
v	Rebates, joints, chamfers, mouldings, grooves, beads, laps, rounded angles, notches, and providing nails, screws, pins, etc.							
vi	Shutters of doors, windows and fan lights shall be measured net in a closed position covering rebates of the frame.							
vii	M.S. hollow frames shall be filled with mortar of masonry while doing masonry work. No extra shall be paid.							
viii	Windows shall be fabricated as per actual opening sizes available at site and as directed.							
ix	All screws for Aluminium works will be Chromium plated steel screws or Aluminium screws as directed.							
x	All Aluminium sections shall have protective covering until completion of other civil works, duly cleaned before handing over. Aluminium work to be preferably done after completion of internal/external plaster.							
xi	All glazing shall be fixed after completing of other works in surrounding area to avoid damage.							

Sr. No.	Particular	Qty	Unit	Rate (Supply)	Total (Supply)	Rate (Labour)	Total (Labour)	Total Supply + Labour
	WOODEN FIRE RATED DOOR FRAMES							
2.1	<p>Providing and fixing wooden fire rated door frames as per BS: 476 part 22, IS:3614 Part II as per the prototype certified by CBRI Roorkee or equivalent lab, frame to be made out of fire rated wood as approved of section 120mm x 70mm for fire resistant doors of 120 minutes fire rating, with heat activated intumescent fire seal strips of size 02 nos. x 10 x 4mm (for smoke sealing) provided in grooves on all three sides of the frame with one coat of approved brand of fire retardant primer including two coats of fire retardant paint FRS 881 un thinned on cleared hard wood surface of door frames (@3.5 sq.m. per litre per coat) including preparation of base surface as per recommendations of manufacturer to make the surface fire retardant, including fixing the frame with 8 nos. 100mm long, 10mm dia metal dash fastners complete as per directions of the Engineer in charge</p> <p>MODE OF MEASUREMENT SHALL BE ONLY FINISHED SURFACE OF DOOR FRAME.</p>	247	Rmt		-			
2.2	Extra for providing 25 x 25 mm matt finish SS angle edging to door frame on the exposed face of 1200 mm height using necessary adhesives/screwes etc all complete	60	Nos		-			
	FIRE RATED DOOR SHUTTERS							

Sr. No.	Particular	Qty	Unit	Rate (Supply)	Total (Supply)	Rate (Labour)	Total (Labour)	Total Supply + Labour
2.3	Supply & fixing of fully insulated wooden fire door of approved make of 120min. fire rating, of minimum 50mm thickness, comprising of 75mm x 44mm hardwood internal timber frame work, with infill insulation of 20mm thick of of 96 kg/m3, wool insulation, coated with intumescent coating on both sides for insulation. The coated insulation shall be sandwiched between min 12mm thick Non Combustible (Calcium Silicate) Boards on both sides (edge to edge on internal Hardwood frame) and clad with 3mm thick Commercial ply & 1mm thick Laminate (approved shade and colour) on both sides, with 50mm x 14mm exposed teak wood lipping all round the shutter. The shutter shall be fitted with fire & smoke intumescent seal of size 20 x 4mm on all the three sides except bottom. The pasting of the ply / laminate should be done using automatic machine and should be free from any nails or perforations.	149	Sqm					
	The board shall be Resistant to vermin, mould growth, minor impact, abrasion and short term water attack and shall be Off -white in colour with a smooth surface suitable to receive most forms of decoration having following technical characters i.e.;; The Construction design similar to NWD12050 and similar to the design tested as per BS 476 part 22 and IS 3614 Part II, at CBRI, Roorkee or equivalent lab. The shutter can be provided with appropriate openings for view panel glass, if required.							
	The door to be fitted on 4 Nos. 4" long SS Hinges (with SS pin) of approved make and completed with Brushed 300mm SS handles of approved make as per the approval of the architect. Cost to be inclusive of all necessary hardware like locks, tower bolts, door stoppers, PVC bushes etc. of approved make and as specified in the drawing.							

Sr. No.	Particular	Qty	Unit	Rate (Supply)	Total (Supply)	Rate (Labour)	Total (Labour)	Total Supply + Labour
2.4	Extra over for providing 40mm x 25mm wide Matt finish SS edge guard - C shape channel to edging to door shutter including necessary adhesives/screws etc all complete.	202	Rmt		-			
	WOODEN SLIDING DOOR							
2.5	Providing and Fixing in position 38 mm thick Sliding Door Shutter made up of approved solid core Flush Door, necessary beading, 1.5 mm thk approved Laminate on both sides of Shutter including necessary hardware, tracks, approved fittings & fixtures like Door Stopper, SS Handle, pelmet to cover tracks. melamine matt polish to all exposed surfaces stained to approved colour & shade, etc. complete as per detail drawing, as specified and as directed by Designer	5	Sqm		-			
2.6	Extra for providing and fixing of vision panel with 6mm thk plain float glass and TW lipping all round both sides of glass panel and finished with approved melamine matt polish etc complete.							
	Size 200 x 800 mm	33	Nos					
2.7	Extra for Providing and Fixing of PVC ventilation grill 150 x 450mm to Toilet door shutter.	13	Nos					
2.8	Extra for using tinted reflective glass of approved shade in place of plain glass.	QRO	Sqm					
2.9	Providing and fixing double action hydraulic floor spring of approved brand and manufacture (conforming to IS:6315) for doors including cost of cutting floors as required, embedding in floors and cover plates, etc., complete.	QRO	Set					

Sr. No.	Particular	Qty	Unit	Rate (Supply)	Total (Supply)	Rate (Labour)	Total (Labour)	Total Supply + Labour
2.10	Providing and fixing SS 304 grade kick plate and Middle Plate 200 mm high on one side or both side as directed including counter sunk screws, buffing etc. complete. Actual plate size used shall be measured and paid for.	30	Sqm					
	SHAFT DOOR							
2.11A	Providing and fixing 19mm thk Composite Marble// Quartz stone Frame to Shaft door opening as per design , etc complete.	5	Rmt		-			
2.11B	Providing and fixing solid core flush doors made of 35mm thk marine ply finished flush Door shutter with necessaary door fixtures as per design details and to be finished in 1mm thk approved laminate on both the sides for Shaft doors.	1	Sqm		-			
	UPVC DGU WINDOW with sliding shutter with allen key access							
2.12	Providing and fixing approved make UPVC section / track framed Window with sliding shutters - DGU glazing using 24 mm thick , hermetically dual sealed, double insulated glass panels comprising of 6 mm thick reflective (Grey / Bronze /Blue /Green) and toughened glass on the outside and 6 mm thick clear toughened float glass on the inside, with 12 mm air gap, complete, with butyl primary sealant and silicone secondary sealant, EPDM gaskets. flashing to ensure resistance to water penetration and air permeability, with allen key access locking etc, complete.	145	Sqm		-			
2.13	Providing and fixing fixed glazing using 10mm thick toughened glass and 12mm thk Quartz stone jamb all around , as per design ,etc complete.	9	Sqm		-			
	TOTAL SECTION 9 - DOORS & WINDOW AND ALLIED WORKS				-			

Sr. No.	Particular	Qty	Unit	Rate (Supply)	Total (Supply)	Rate (Labour)	Total (Labour)	Total Supply + Labour
3.00	PARTITION & PANELLING WORK.							
3.1	Providing and fixing bed head wall panelling in 12 mm thk ply panelling / Boxing of AL. box section 50x35 mm fixed over finished wall surface to hide over MGPS service line to BED Head panel assembly as per drawing details, finished in 1 mm thick laminate of approved shade. Including SS strips 10 m mx 3 mm thick, necessary hardware, glue etc all complete. (Location :- ICU Beds)	150	Sqm		-			
3.2	Providing and constructing Work table of size/module as per detailed drawing with 30mm thk table top 600mm[w] x 750 mm [ht] and front panel, sides, etc in 19mm thk commercial ply and finished in 1mm thick laminate on top and underside in 0.8mm thick. Edges to be in T.W beading polish.Supports, to be in ply boxing and finished in approved laminate.1 Nos. of pedestal 400mm wide for work table consisting of 2 drawers of 100mm ht balance openable shutter and skirting 100 mm ht finished in approved laminate as per detail drgs,all external surface finished in approved 1mm thk laminate and inside in 0.8mm thk white laminate. Cost to including handles,locks,hinges,telescopic channels, buffer with leveler, wire manager, etc complete.							
3.2a	Linear Workstation [L]X600mm[W]x750mm[H] - Refer dwg CF-07	18	RMT		-			
3.2b	L shaped work table - 1500mm[L]X700mm[W]x750mm[H] with side table 1000mm[L]x375mm[W]x750mm[H] -Refer Dwg CF-01	3	Nos.		-			

Sr. No.	Particular	Qty	Unit	Rate (Supply)	Total (Supply)	Rate (Labour)	Total (Labour)	Total Supply + Labour
3.3	Providing and constructing Nurse Station / Resistration table of size as per Dwg. Working Table top in 19mm commercial ply and First Tier top and 2nd tier Work top finished in 6mm thk approved shade Solid Mineral Surface (Dupont) and including edges, 100 mm high skirting in 6mm thk Solid mineral surface material and all other surfaces in 1mm th laminate, Counter top as per Dwg in "L" shape with rounded edge. The rate to include three nos of pedestal units of size 400 x 600 x 750mm with 3 drawers and finished in approved laminate 1 mm thick for external surfaces and 0.8 mm thick laminate for internal surfaces. Rate also to include Pigeon hole type storage in 19mm marine ply of 300mm high at table top area. Cost also to include handles, telescopic channels, Buffer with leveler, 35 mm dia., wire manager etc. NURSE STATION. REFER Dwg CF-14							
03.3A	NURSE STATION (L MM) X 600MM WIDE x 750mm [H]	24	RMT		-			
3.4	Providing and fixing storage unit in 19mm marine ply for shutters, verticals and shelves, backing in 12 mm ply, all external surfaces finish in 1mm laminate , insides in 0.8 mm thick plain white laminate, cost to include for all hardware, lipping patti, handles, hinges, locks, etc.100 mm Skirting in ply with approved laminate to be provided at bottom. Area in elevation to be measured for payment (commercial Ply)							
3.4a	400mm~600mm deep Full Ht Storage. Refer Dwg - CF 11,23,24	109	Sqm		-			
3.4b	400mm~600mm deep Low Ht Storage. Refer Dwg CF-03.	5	Sqm		-			

Sr. No.	Particular	Qty	Unit	Rate (Supply)	Total (Supply)	Rate (Labour)	Total (Labour)	Total Supply + Labour
3.5	Providing and fixing in position Over Head storage 400mm deep ,750mm ht made out of 19 mm thk 6mm thk frosted glass shutter with matt finish aluminum profile handle at the bottom as per detailed drawing. The unit shall comprise of Shelves inside and recessed pelmet for light to be provided at bottom towards wall. All external finishes finished in 1mm thk laminate, insides in 0.8 mm thick plain white laminate, cost to include for all hardware, lipping patti, handles, hinges, locks, magnets etc complete. Refer Dwg CF-08	13	Sqm		-			
3.6	Providing and fixing in position Soft board paneling on wall between desk / workstation top and overhead storages. Nominal framing of hard wood to be fixed on wall and 6 mm thk ply to be boarded on framing. 12 mm thk Soft Board to be boarded on ply finished with approved Fabric. 150mm high ply band finished in approved shade of 1mm thk laminate to be provided at bottom as per detailed drawing. Refer Dwg CF-01,CF-07	14	Sqm		-			
	CHANGE ROOM CUBILE							

Sr. No.	Particular	Qty	Unit	Rate (Supply)	Total (Supply)	Rate (Labour)	Total (Labour)	Total Supply + Labour
3.7	Providing and Fixing in position Modular Partition system of approved make, 18mm solid compact laminate panels including doors of Freshcolour Titian series of BESCO & MERINO make or equivalent conforming to ISO 2046 as per the detail drawings. This also includes providing and fixing in position necessary SS hardware with Nylon finish as per manufacturers specifications & Architects instructions like handles, hinges, latches, indicators, top rail, connectors, hooks, knobs, brackets, U channels, thumbturn, locks, SS fittings, SS pedestal / adjustable foot, top rail, channel, privacy lock, accessories, Bushing, necessary hardware, approved adhesive, gaskets, scaffolding, cleaning, etc. complete as per detail drawing, as specified and as directed by Designer. (size 1000 x 1000)	6	Nos		-			
3.8	Providing and fixing 8mm thk Calicium silicate board wall panelling using 35mm thk GI channel framework, including jointing tapes, counter sunk SS screws, necessary hardware etc all complete.- over existing Vitrified Dado to receive Vinyl Wall flex.	325	Sqm		-			
3.9	Providing and fixing mirror of size as per drawings using 6mm thick mirror of approved make cut to required sizes fixed with 3M or BOW tapes on a backing of 12mm thick Marine plywood, ply fixed on wall with necessary screws to wall/partitions. All edges of the mirror to be machine polished.							
3.10a	Mirror of size 600 mm x 1200mm - (In change Rm)	6	Nos.		-			
3.10b	Mirror of size 500 mm x 750mm - (In Toilet)	9	Nos.		-			

