



MAHATMA GANDHI MISSION TRUST
MGM INSTITUTE OF HEALTH SCIENCES, CENTRAL PURCHASE DEPARTMENT (CPD)
Plot 1 &2, Sector -1 Kamothe, Navi Mumbai 410209

4. E-Tender for Nurse Call System.

Tenders invited from reputed Manufactures or their authorised distributors / dealers of Nurse Call System at MGM Hospital, Sanpada, Navi Mumbai in the format given bellow:

Name & Address of Vendor: _____

NOTES:	Project Name	MGM HOSPITAL, SANPADA
	Subject	Bill of Quantities for Nurse Call System
	1) I.R or R.O. means Item Rate Only.	
	2) In case of any discrepancy between the drawings, specifications and the BOQ, the BOQ shall be considered for the tender.	
	3) Description of the items here in are brief. Contractor shall supply and install all accessories, supports, consumables as per specifications and / or as required to complete the system. Rates shall include provision of all such components.	
	4) 'S' under Rate and Amount shall mean Supply only. 'ITC', under Rate and Amount shall mean Installation, Testing, Commissioning including supply of installation all required accessories and consumables with Wastage on materials and labour.	
	5) Loading, transporting, unloading, handling/double handling, hoisting to all levels, setting, fitting and fixing in position, protecting, disposal of debris and all other labour necessary in and for the full and entire execution and for the job in accordance with the contract documents, good practice and recognize principles.	
	6) The Contractor shall procure and bring Materials/Equipment to the site only on the basis of drawings approved for construction and shop drawings and not on the basis of Schedule of Quantities which are approximate only. This also applies to the Contractor's requisition for Owner supplied materials.	
	7) The unit rate for all local equipment or materials (not being procured against duty benefit) in Indian Rupees shall include cost of equipment and materials including all taxes and duties and also including forwarding, freight, insurance and transport into Contractor's store at site, storage, installation, testing, balancing, commissioning and other works required.	
	Approved makes : Edifice Medical System / Medisystem / Schrack	

Sr. No.	Item Particular	Qty	UNIT	Rate Per Unit		Total Amount		GST %
				Supply	Installation	Supply	Installation	
A	<u>NURSE CALL SYSTEM</u>							
	Design, Supply, Install, Testing ,Commissioning of all Nurse Calling System complete with all items mentioned but not limited to below , In general the complete system design and installations shall confirm to latest guidelines and the specifications, drawings submitted here with. Note : All Equipment items for Nurse call System shall be according to Approved vendor by Client.							
A.1	Nurse Station Console Unit							
	Addressable Microprocessor Control Nurses Call Station Monitor with built-in 7 Segment LED and a soft buzzer. Information displayed in 5 digit, when more then one call is registered, then the information shall be scrolled. Power supply suitable for 220 volts 50 hz AC main supply complete with step-down transformer of appropriate rating , electronic rectifier with regulating circuits to give two numbers of DC outputs of + 12V DC through battery/panel and battery charger , all housed in powder coated sheet steel enclosure ,network interface module, power supply and complete as per specification required. The Staff Console shall have a 7" capacitive touch backlit color LCD screen.	3	Nos					
A.2	Nurse Call Bed Unit							
1	Supply, Installation, Testing & Commissioning of Bedside modules comprising of Nurse call, cancel & Wait,Code blue buttons hand held unit and input jack for hand held module including providing and fixing of 1.6 mm thick GI box complete as per specifications.	31	Nos					
2	Supply, Installation, Testing & Commissioning of Bedside modules comprising of Code blue Module including providing and fixing of 1.6 mm thick GI box complete as per specifications.	31	Nos					
A.3	Toilet Units							
1	Supply, Installation, Testing & Commissioning of Emergency Switch aNear WC including providing and fixing of GI box complete with all accessories and as per specifications	5	Nos					
2	Supply, Installation, Testing & Commissioning of Shower Pull cord Unit complete with all accessories and as per specifications.	61	Nos					
A.3	Door Display Unit							

